# VERTICAL PACKAGING AND TRANSPORT INFORMATION FOR Q CELLS SOLAR MODULES Q.PEAK DUO-G6.X+ · Q.PEAK DUO BLK-G6.X+ · B.LINE PEAK DUO-G6.X · B.LINE PEAK DUO BLK-G6.X

SCOPE OF DELIVERY	
Scope of delivery	<ul> <li>Solar modules in box (as described below)</li> <li>1× delivery receipt with specifications of pallet numbers (box IDs)</li> <li>1× safety information</li> <li>1× packing list with Module ID numbers on each box</li> </ul> Measured module current-voltage parameters ("flasher list") are sent parallel to the delivery per email.
Handling units	The smallest handling unit is a completely filled transport box, as described below. A partially filled transport box will only be sent in special cases after prior agreement (may involve additional costs).

## TECHNICAL DATA PACKAGING / STACKABILITY

Box type	Corrugated board container on wooden pallet, 120 cell modules in the version of 32 modules per pallet
Outer dimensions (incl. pallet)	approx. $71.5 \times 45.3 \times 48.0$ in $(1815 \times 1150 \times 1220$ mm)
Approx. tare weight	101.4 lbs (46 kg)
Box outside view	



Box	inside view	



Modules per box	32
Approx. gross weight (full box)	1505 lbs (683 kg)
Max. no. of stacked boxes for transport	1 on 1 (batch of 2)
Max. no. of stacked boxes for storage	2 on 1 (batch of 3)

### LOADING

LOADING		
Typical truck loading 53' trailer (47' 6" × 98.5" × 108")	28 pallets (14 × 2 lengthwise) Maximum allowed volume	
Typical 40' high cube container load (26 tons; 39'6"–39'6.8" × 7'7.7"–7'8.9" × 8'9.5")	24 pallets (12 × 2 lengthwise) Maximum allowed volume	
Truck specification and transit support		Q CELLS conducts pre-delivery check of all trucks. Generally, only trucks are



Q CELLS conducts pre-delivery check of all trucks. Generally, only trucks are approved for loading which are roadworthy and ready for operation. Q CELLS loads, stores and fastens the goods safe for transport. The carrier must approve of the safe storage. The load securing complies to the state of the art in accordance with the respective legal regulations (e.g. Road Traffic Act). The carrier must provide appropriate tools for securing the load. Trucks without appropriate equipment to secure the load will not be loaded and will be prohibited to transport the modules. For ecological reasons, Q CELLS always aspires a complete loading of the truck.



## HORIZONTAL PACKAGING AND TRANSPORT INFORMATION FOR Q CELLS SOLAR MODULES Q.PEAK DUO-G6.X+ · Q.PEAK DUO BLK-G6.X+ · B.LINE PEAK DUO-G6.X · B.LINE PEAK DUO BLK-G6.X

SCOPE OF DELIVERY	
Scope of delivery	<ul> <li>Solar modules in box (as described below)</li> <li>1× delivery receipt with specifications of pallet numbers (box IDs)</li> <li>1× safety information</li> <li>1× packing list with Module ID numbers on each box</li> </ul> Measured module current-voltage parameters ("flasher list") are sent parallel to the delivery per email.
Handling units	The smallest handling unit is a completely filled transport box, as described below. A partially filled transport box
	will only be sent in special cases after prior agreement (may involve additional costs).

## TECHNICAL DATA PACKAGING / STACKABILITY


Box type	120 cell modules in the version of 32 modules per wooden pallet
Outer dimensions (incl. pallet)	approx. $70.1 \times 42.5 \times 47.6$ in $(1780 \times 1080 \times 1208$ mm)
Approx. tare weight	81.57lbs (37kg)
Box outside view	



Modules per box	32
Approx. gross weight (full box)	1485 lbs (674 kg)
Max. no. of stacked boxes for transport	1 on 1 (batch of 2)
Max. no. of stacked boxes for storage	2 on 1 (batch of 3)

#### LOADING

Typical truck loading 53' trailer (47' 6" × 98.5" × 108")	28 pallets (14 × 2 lengthwise) Maximum allowed volume
Typical 40' high cube container load (26 tons; 39'6"–39'6.8" × 7'7.7"–7'8.9" × 8'9.5")	26 pallets (12 × 2 lengthwise, 1 × 2 crosswise)  Maximum allowed volume





Q CELLS conducts pre-delivery check of all trucks. Generally, only trucks are approved for loading which are roadworthy and ready for operation. Q CELLS loads, stores and fastens the goods safe for transport. The carrier must approve of the safe storage. The load securing complies to the state of the art in accordance with the respective legal regulations (e.g. Road Traffic Act). The carrier must provide appropriate tools for securing the load. Trucks without appropriate equipment to secure the load will not be loaded and will be prohibited to transport the modules. For ecological reasons, Q CELLS always aspires a complete loading of the truck.

#### Hanwha Q CELLS America Inc.

400 Spectrum Center Drive, Suite 1400, Irvine, CA 92618, USA | TEL +1 949 748 59 96 | EMAIL inquiry@us.q-cells.com | WEB www.q-cells.us

