Q.TRON M-G2.X B.LINE TRON M-G2.X



Packaging and transport information for Qcells solar modules

Scope of delivery			
Scope of delivery	■ Solar modules in box (as described below)		
	1× delivery receipt with specifications of pallet numbers (box IDs)		
	■ 1× safety information		
	■ 1× packing list with Module ID numbers on each box		
	Measured module current-voltage parameters ("flasher list") are sent parallel to the delivery per email.		
Scope of delivery	The smallest handling unit is a completely filled transport box, as described below. A partially filled transport box will only be sent in special cases after prior agreement (may involve additional costs).		

Technical data packaging / stack	ability		
Package type	108 cell modules in the version of 36 / modules per galvanized wooden pallet		
Outer dimensions (incl. pallet)	approx. 70.1 × 46.7 × 50.9 in (1780 × 1185 × 1292 mm)		
Approx. tare weight	46.7 lbs (21.2 kg)		
Package image			



Modules per pallet	36	36		36				
Approx. gross weight (full box)	1770.8 lbs (803.2kg) for	Q.TRON M-G2+	Q.TRON BLK M-G2+					
		BLINE TRON M-G2+	BLINE TRON BLK M-G2+					

Max. no. of stacked boxes for transport	1 on 1 (batch of 2)
Max. no. of stacked boxes for storage	2 on 1 (batch of 3)

Max. no. of stacked boxes for storage 2 on 1 (batch of 3) Loading

Typical truck loading 53' trailer	24 pallets (12 × 2 lengthwise)
(52'6" × 8'2" × 8'5")	Maximum allowed volume

Typical 40' high cube container load 12 pallets (6 × 2 lengthwise) (26 tons; 39'6"–39'6.8" × 7'7.7"–7'8.9" × 8'9.5") Maximum allowed volume

Truck specification and transit support



Qcells conducts pre-delivery check of all trucks. Generally, only trucks are approved for loading which are roadworthy and ready for operation. Qcells loads, stores and fastens the goods safe for transport. The carrier must approve of the safe storage. The load securing complies to the state of the art in accordance with the respective legal regulations (e.g. Road Traffic Act). The carrier must provide appropriate tools for securing the load. Trucks without appropriate equipment to secure the load will not be loaded and will be prohibited to transport the modules. For ecological reasons, Qcells always aspires a complete loading of the truck.

